

BID PROPOSAL
STORM DRAINAGE IMPROVEMENTS
ROOSEVELT COUNTY FAIRGROUNDS
CITY OF PORTALES, NEW MEXICO
MAY 13, 2021

CONSTRUCTION BID ITEMS

ITEM NO.	DESCRIPTION	APPROX. QUANTITY	UNIT BID PRICES	AMOUNT BID
1.	UNCLASSIFIED EXCAVATION & HAUL (3 BASINS AND ENTRYWAY) AT _____ C.Y.	4,708.0		
2.	SUBGRADE PREPARATION & GRADING AT _____ S.Y.	11,925.0		
3.	BASE COURSE – 6" DEPTH AT _____ S.Y.	1,970.0		
4.	DOUBLE PENETRATION CHIP SEAL COAT (5/8" & 3/8" AGGREGATE) AT _____ S.Y.	12,525.00		
5.	INVERTED GRASSY SWALE SECTION (10' WIDTH) AT _____ S.Y.	1,280.0		
6.	CONCRETE SWALE (6" X 8') AT _____ S.Y.	380.0		
7.	MEDIAN DROP INLET WITH 10' X 10' CONCRETE PAD AT _____ EA.	3.0		
8.	MEDIAN DROP INLET WITH 5'X 5' CONCRETE PAD EA.	2.0		
9.	RIP – RAP (CLASS "A" – WIRE WRAPPED) AT _____ EA.	3.0		
10.	8'-CONCRETE RUNDOWN SECTION - 6" RPCC AT _____ S.Y.	205.0		
11.	CSP – 8" DIAMETER (IN-PLACE) AT _____ L.F.	600.0		
12.	CSP – 12" DIAMETER (IN-PLACE) AT _____ L.F.	870.0		
13.	CONCRETE JUNCTION BOX (3'x5'x3' DEPTH) AT _____ EA.	1.0		
14.	CHAIN LINK FENCE – 4' HEIGHT (NMDOT SECTION 607.2.3) AT _____ L.F.	1,100.0		

BID PROPOSAL
STORM DRAINAGE IMPROVEMENTS
ROOSEVELT COUNTY FAIRGROUNDS
CITY OF PORTALES, NEW MEXICO
MAY 13, 2021

CONSTRUCTION BID ITEMS

ITEM NO.	DESCRIPTION	APPROX. QUANTITY	UNIT BID PRICES	AMOUNT BID
15.	CHAIN LINK FENCE GATE 4' HEIGHT (NMDOT SECTION 607.2.3.6) AT _____ EA.	2.0		
16.	GRADING AND SEEDING-CLASS "C" AT _____ S.Y	3,800.00		
17.	CONSTRUCTION STAKING BY CONTRACTOR AT _____ L.S.	1.0		
18.	MOBILIZATION AT _____ L.S	1.0		
	SUB-TOTAL			
	TAX (8.1875%)			
	TOTAL BID			

Contractors Name & N.M. License No.

06-01-2021

DATE